



PRIMROSE PARK

PASSIVHAUS SCHEME

- 1. Introductions**
- 2. The Project**
- 3. Some Development Facts**
- 4. The Passivhaus Standard**
- 5. To Certify or Not To Certify**
- 6. The Challenges**
- 7. The Solutions**
- 8. Construction Techniques**
- 9. Commercial Facts**
- 10. Post Construction Monitoring**
- 11. Questions**

CONTENTS





Introduction

Andrew Lawrie

Plymouth Community Homes

David Pengelly

Mi-space



The Project

- Plymouth CC 'Get Plymouth Building' Site
- Transferred £1 for Passivhaus Project
- Homes England – higher grant +£8kpu
- 72 Affordable Homes
 - 23 Shared Ownership
 - 49 Affordable Rented
 - 6 x 1 Bed Flats
 - 66 x 2 & 3 Bed Houses

Scheme	Plot Price	Works/ unit	Fees/ Unit	TSC/ Unit	Grant/ Unit
Ham Drive	4,529	110,143	13,695	128,367	18,824
Southway Campus	7,015	119,481	24,378	150,874	31,776
Southway Primary	1,842	123,787	25,053	149,519	34,997
Bodmin Rd Passivhaus	0	141,264	19,685	160,949	39,630
Mean:	2,854	126,928	22,696	152,041	31,307

Development Facts

- Energy Requirement – Less than 15kWh/m²yr
- Floors - 0.035W/mK
- Walls - u-value of 0.150W/m²K
- Roofs - 0.094W/m²K
- Air Tightness – 0.6 @ n50 (Actual 0.4)
- MVHR- System Air VTC 200
- Boiler - Worcester GS 25i ERP
- Windows – PCH Synseal UPVC Triple Glazed





The Passivhaus Standard

Air-tightness	0.6ach @ 50Pa	← Comfort & Energy
Surface temp (windows)	>17degC	← Comfort
Summer overheating	Max 10% >25degC	← Comfort
Vent	~30m ³ /hr.person	← Comfort
Heating and cooling	15kWh/m ² yr @20C Or 10 W/m ² Heating Load	← Energy
Primary Energy	120kWh/m ² yr	← Energy



To Certify, or Not to Certify

Passivhaus Principles?

Or

Passivhaus Certified?

We have been asked this question several times and having now had the benefit of delivering some units I would state that the single largest benefit Passivhaus Certification brings is the robust validation process you go through. It holds the whole team to a standard that you cannot escape.



The Challenges

- **Client**

- **Lack of Experience** – visits/talks etc but just do it!
- **Selecting a Team** – previous experience
- **Procurement Route** – 2-Stage process
- **Board Approval** – cost and rent cut

- **Contractor**

- Fear – Lack of knowledge & Misconceptions
- Air Tightness
- Product Selection
- Certification
- Clarity from Passivhaus Consultants



The Solutions - Contractor

- Fear – Lack of knowledge bring the supply chain on journey & train.
- Air Tightness – Keep it simple direct delivery team
- Product Selection – Challenge everything accept nothing at face value
- Certification – Records, Records, Records and robust QA Plan & understanding the Audit process
- Clarity from Passivhaus Consultants – Persistence, developing relationships and turning the jargon into simple and clear solutions



Construction Techniques

Various construction methodologies were design tested on the criteria of:



- **Passivhaus Principles**
 - Ease of achieving high insulation
 - Ease of achieving air tightness
- **Cost**
 - A key client driver was in achieving value for money
- **Buildability**
 - Ensuring our local supply chain could deliver the scheme
 - No complicated detailing

Construction Techniques

Simplicity

During the design development phase we came to understand the necessity to keep everything as simple as we could and whilst various other solutions for the construction methodology were tested the solution of a block leaf laid flat with an internal parge plaster coat and an external insulation render system met this key driver.

Other systems considered included off site SIP, Composite Panels and timber frames, however for us these all brought complexity and the associated increased risks.



Typical Living / Dining & Bedroom window.

Commercial Facts

When considering Passivhaus you will need to think about the investment costs, however keeping the principle of simplicity in mind the extra over costs need not be extreme. At this scheme our assessment is as the table below.

We firmly believe that a cost increase of around 5% is achievable when keeping to the simplicity theme. The more complex the building the more the cost increase will be.

Areas of further cost savings are –

- Omit back up heating system
- Use membranes instead of smart ply
- Use of Non Passivhaus Certified products



BN040 BODMIN ROAD PASSIVHAUS EXTRA OVER COSTS			Total Cost	Abnormal Costs	Abnormal Free Cost	E/O For Passivhaus	E/O For Passivhaus
			£10,400,000.00	£650,000.00	£9,750,000.00	£772,877.32	7.93%
SITE	5358	M2	£1,941.02	£121.31	£1,819.71	£144.25	7.93%
PLOT	72	Nr	£144,444.44	£9,027.78	£135,416.67	£10,734.41	7.93%
Elements Of Increased Costs	Supervision & Programme Implications	Parge Coat	Air Tightness	MVHR	Windows premium against Double Glass	MVHR Roof Penetrations and Weathering	Totals
	£30.00	£15.00	£28.91	£50.25	£15.68	£4.41	£144.25



Post Construction Monitoring

Post occupancy monitoring of Primrose Park

- Direct comparison of Passivhaus against a similar sized Building Regulations compliant scheme developed by PCH, both completed in 2018
- In-depth monitoring of 20 houses from each site including:
 - Internal conditions logged (temperature and humidity hourly)
 - Regular questionnaires
 - Energy readings
- The monitoring will run for 2 years

Would we do it again? & Other questions.